

DEPARTMENT OF  
**CITY PLANNING**  
200 N. SPRING STREET, ROOM 525  
LOS ANGELES, CA 90012-4801  
AND  
6262 VAN NUYS BLVD., SUITE 351  
VAN NUYS, CA 91401  
CITY PLANNING COMMISSION

DAVID H. J. AMBROZ  
PRESIDENT

RENEE DAKE WILSON  
VICE-PRESIDENT

ROBERT L. AHN  
MARIA CABILDO  
CAROLINE CHOE  
RICHARD KATZ  
JOHN W. MACK  
DANA M. PERLMAN  
MARTA SEGURA

JAMES K. WILLIAMS  
COMMISSION EXECUTIVE ASSISTANT II  
(213) 978-1300

**CITY OF LOS ANGELES**  
CALIFORNIA



ERIC GARCETTI  
MAYOR

**EXECUTIVE OFFICES**  
200 N. SPRING STREET, ROOM 525  
LOS ANGELES, CA 90012-4801

MICHAEL J. LOGRANDE  
DIRECTOR  
(213) 978-1271

LISA M. WEBBER, AICP  
DEPUTY DIRECTOR  
(213) 978-1274

JAN ZATORSKI  
DEPUTY DIRECTOR  
(213) 978-1273

FAX: (213) 978-1275

INFORMATION  
[www.planning.lacity.org](http://www.planning.lacity.org)

Decision Date: August 28, 2015

Appeal End Date: September 8, 2015

Benny Silva (O/A)  
563 South Brand Boulevard  
San Fernando, CA 91340

Richard Prutz (R)  
Prutz & Associates  
2942 Scott Road  
Burbank, CA 91504

Re: Case No. TT-53664  
Related Case: None  
13600 North Fenton Avenue  
Community Plan: Sylmar  
Zone : (T)(Q)RE11-1-K  
D.M. : 228-B-153, 228-B-157  
C.D. : 7  
CEQA : ENV-2013-2361-MND  
Legal Description: Portion of Block 16,  
Maclay Rancho Mission Tract

In accordance with provisions of Section 17.03 of the Los Angeles Municipal Code (LAMC), the **Advisory Agency adopted Mitigated Negative Declaration ENV-2013-2361-MND as the environmental clearance and approved Tentative Tract No. 53664, located at 13600 N. Fenton Avenue for a maximum six lots as shown on map stamp-dated August 5, 2013 in the Sylmar Community Plan.** This unit density is based on the RE11-1VL Zone. (The subdivider is hereby advised that the LAMC may not permit this maximum approved density. Therefore, verification should be obtained from the Department of Building and Safety which will legally interpret the Zoning Code as it applies to this particular property.) The Advisory Agency's approval is subject to the following conditions:

**NOTE(S)** on clearing conditions: When two or more **agencies** must clear a condition, subdivider should follow the sequence indicated in the condition. For the benefit of the applicant, subdivider shall maintain record of all conditions cleared, including all material supporting clearances and be prepared to present copies of the clearances to each reviewing agency as may be required by its staff at the time of its review.

**BUREAU OF ENGINEERING - SPECIFIC CONDITIONS**

1. That a 2-foot wide strip of land be dedicated along Fenton Avenue adjoining the subdivision to complete a 32-foot wide half right-of-way. In the event the **LA Mobility Plan 2035** is in affect at the time of the final map recordation, then a 3-foot wide strip of land be dedicated to complete a 33-foot wide half right-of-way.
2. That all existing public sanitary sewer and drainage easements be clearly shown on the final map.
3. That a Covenant and Agreement be recorded advising all future owners and builders that prior to issuance of a building permit, a Notice of Acknowledgment of Easement must be recorded and an application to do work in any drainage and/or sewer easements and to construct over the existing drainage facilities must be submitted to the City Engineer for approval.

**DEPARTMENT OF BUILDING AND SAFETY, ZONING DIVISION**

4. That prior to recordation of the final map, the Department of Building and Safety, Zoning Division shall certify that no Building or Zoning Code violations exist on the subject site. In addition, the following items shall be satisfied:
  - a. Provide a copy of affidavit AF-05-180237. Show compliance with all the conditions/requirements of the above affidavit as applicable.
  - b. Show all street dedication(s) as required by Bureau of Engineering and provide the net lot area after all dedication. "Area" requirements (minimum 11,000 square foot of lot area and minimum 70 foot. lot width) shall be re-checked after the required street dedication.

**Notes:**

Any proposed structures or uses on the site have not been checked for and shall comply with Building and Zoning Code requirements. Plan check will be required before any construction, occupancy or change of use.

An appointment is required for the issuance of a clearance letter from the Department of Building and Safety. The applicant is asked to contact Laura Duong at (213) 482-0434 to schedule an appointment.

**DEPARTMENT OF BUILDING AND SAFETY, GRADING DIVISION**

- 5 That prior to issuance of a grading or building permit, or prior to recordation of the final map, the subdivider shall make suitable arrangements to assure compliance, satisfactory to the Department of Building and Safety, Grading Division, with all the requirements and conditions contained in Inter-Departmental Letter dated June 12, 2015, Log No. 85215-01 and attached to the case file for Tract No. 53664.

**DEPARTMENT OF TRANSPORTATION**

6. That the project be subject to any recommendations from the Department of Transportation, prior to recordation of the final map.

**FIRE DEPARTMENT**

- 7.. That prior to the recordation of the final map, a suitable arrangement shall be made satisfactory to the Fire Department, binding the subdivider and all successors to the following:
  - a. Submittal of plot plans for Fire Department review and approval prior to recordation of Tract Map Action.

**DEPARTMENT OF WATER AND POWER**

- 8.. Satisfactory arrangements shall be made with the Los Angeles Department of Water and Power (LADWP) for compliance with LADWP's Water System Rules and requirements. Upon compliance with these conditions and requirements, LADWP's Water Services Organization will forward the necessary clearances to the Bureau of Engineering. (This condition shall be deemed cleared at the time the City Engineer clears Condition No. S-1.(c).)

**BUREAU OF STREET LIGHTING**

*Street Lighting clearance for this Street Light Maintenance Assessment District Condition is conducted at 1149 South Broadway Suite 200, 213-847-1341. Street Lighting improvement condition clearance will be conducted at the Bureau of Engineering District Office. Contact 213-847-1547 for information regarding the street lighting design/plan.*

9. Street Lighting clearance for this Street Light Maintenance Assessment District condition is conducted at 1149 S. Broadway Suite 200. Street Lighting improvement condition clearance will be conducted at the Bureau of Engineering District office, see condition S-3. (c).

Prior to the recordation of the final map or issuance of the Certificate of Occupancy (C of O), street lighting improvement plans shall be submitted for review and the owner shall provide a good faith effort via a ballot process for the formation or annexation of the property within the boundary of the development into a Street Lighting Maintenance Assessment District.

**BUREAU OF SANITATION**

10. Satisfactory arrangements shall be made with the Bureau of Sanitation, Wastewater Collection Systems Division for compliance with its sewer system review and requirements. Upon compliance with its conditions and requirements, the Bureau of Sanitation, Wastewater Collection Systems Division will forward

the necessary clearances to the Bureau of Engineering. (This condition shall be deemed cleared at the time the City Engineer clears Condition No. S-1. (d).).

#### **INFORMATION TECHNOLOGY AGENCY**

11. That satisfactory arrangements be made in accordance with the requirements of the Information Technology Agency to assure that cable television facilities will be installed in the same manner as other required improvements. Refer to the Los Angeles Municipal Code (LAMC) Section 17.05-N. Written evidence of such arrangements must be submitted to the Information Technology Agency, 200 N. Main Street, Room 1255, Los Angeles, CA 90012, (213) 473-9973.

#### **DEPARTMENT OF RECREATION AND PARKS**

12. That the Quimby fee be based on the RE11 Zone.

#### **DEPARTMENT OF CITY PLANNING - SITE SPECIFIC CONDITIONS**

13. Prior to the recordation of the final map, the subdivider shall prepare and execute a Covenant and Agreement (Planning Department General Form CP-6770) in a manner satisfactory to the Planning Department, binding the subdivider and all successors to the following:
  - a. Limit the proposed development to a maximum of six (6) lots.
  - b. Provide a minimum of 2 covered off-street parking spaces per dwelling unit. Lots with less than a 50 foot frontage shall have one guest parking provided on site.
  - c. That prior to issuance of a certificate of occupancy, a minimum 6-foot-high slumpstone or decorative masonry wall shall be constructed adjacent to neighboring residences and alleys, if no such wall already exists, except in required front yard.
  - d. That a solar access report shall be submitted to the satisfaction of the Advisory Agency prior to obtaining a grading permit.
  - e. That the subdivider consider the use of natural gas and/or solar energy and consult with the Department of Water and Power and Southern California Gas Company regarding feasible energy conservation measures.
  - f. The applicant shall defend, indemnify and hold harmless the City, its agents, officers, or employees from any claim, action, or proceeding against the City or its agents, officers, or employees relating to or to attack, set aside, void or annul this approval which action is brought within the applicable limitation period. The City shall promptly notify the applicant of any claim, action, or proceeding and the City shall cooperate fully in the defense. If the City fails to promptly notify the applicant of any

claim action or proceeding, or if the City fails to cooperate fully in the defense, the applicant shall not thereafter be responsible to defend, indemnify, or hold harmless the City.

#### **DEPARTMENT OF CITY PLANNING-ENVIRONMENTAL MITIGATION MEASURES**

14. That prior to recordation of the final map, the subdivider shall prepare and execute a Covenant and Agreement (Planning Department General Form CP-6770 and Exhibit CP-6770. M) in a manner satisfactory to the Planning Department requiring the subdivider to identify (a) mitigation monitor(s) who shall provide periodic status reports on the implementation of mitigation items required by Mitigation Condition No(s), 15, and 16 of the Tract's approval satisfactory to the Advisory Agency. The mitigation monitor(s) shall be identified as to their areas of responsibility, and phase of intervention (pre-construction, construction, postconstruction/maintenance) to ensure continued implementation of the above mentioned mitigation items.
15. Prior to the recordation of the final map, the subdivider will prepare and execute a Covenant and Agreement (Planning Department General Form CP-6770) in a manner satisfactory to the Planning Department, binding the subdivider and all successors to the following:

#### **Habitat Modification (Nesting Native Birds, Non-Hillside or Urban Areas)**

- MM-1 Nesting Native Birds – The project may result in the removal of vegetation and disturbances to the ground and therefore may result in the taking of nesting bird species. Migratory native bird species are protected by international treaty under the Federal Migratory Bird Treaty Act (MBTA) of 1918. Sections 3503, 3503.5, and 3513 of the California Fish and Game Code prohibit the taking of all birds and their active nests including raptors and other migratory nongame birds (as listed under the Federal MBTA).
- a. Proposed project activities (including disturbances to native and non-native vegetation, structures and substrates) should take place outside of the breeding bird season which generally runs from March 1 – August 31 (as early as February 1 for raptors) to avoid taking (including disturbances which would cause abandonment of active nests containing eggs and/or young). Take means to hunt, pursue, catch, capture or kill, or attempt to hunt, pursue, catch, capture or kill (Fish and Game Code Section 86).
  - b. If project activities cannot feasibly avoid the breeding bird season, beginning thirty days prior to the disturbance of suitable nesting habitat the applicant shall:
    - i. Arrange for weekly bird surveys to detect any protected native birds in the habitat to be removed and any other habitat within 300 feet of the construction work area (within

500 feet for raptors) as access to adjacent areas allows. The surveys shall continue on a weekly basis with the last survey being conducted no more than 3 days prior to the initiation of clearance/construction work.

- ii If a protected native bird is found, the applicant shall delay all clearance/construction disturbance activities within 300 feet of suitable nesting habitat (within 500 feet for suitable raptor nesting habitat) until August 31.
- iii Alternatively, the Qualified Biologist could continue the surveys in order to locate any nests. If an active nest is located, clearing and construction within 300 feet of the nest (within 500 feet for raptor nests) or as determined by a qualified biological monitor, shall be postponed until the nest is vacated and juveniles have fledged and when there is no evidence of a second attempt at nesting. The buffer zone from the nest shall be established in the field with flagging and stakes. Construction personnel shall be instructed on the sensitivity of the area.
- iv. The applicant shall record the results of the recommended protective measures described above to document compliance with applicable State and Federal laws pertaining to the protection of native birds.

#### **Tree Removal (Non-Protected Trees)**

- MM-2 Prior to the issuance of any permit, a plot plan shall be prepared indicating the location, size, type and general condition of all existing trees on the site and within the adjacent public right(s)-of-way.
- MM-3 All significant (8-inch or greater trunk diameter, or cumulative trunk diameter if multi-trunked, as measured 54 inches above the ground) non-protected trees on the site proposed for removal shall be replaced on a 1:1 ratio with a minimum 24 inch box tree. Net, new trees, located within the parkway of the adjacent public right(s)-of-way, may be counted toward replacement tree requirements.
- MM-4 Removal of all trees in the public right-of-way shall require approval of the Board of Public Works. Contact: Urban Forestry Division at: 213-847-3077. All trees in the public right-of-way shall be provided per the current standards of the Urban Forestry Division, Bureau of Street Services, Department of Public Works, Bureau of Street Services.

**Seismic**

- MM-5 The design and construction of the project shall conform to the Uniform Building Code seismic standards as approved by the Department of Building and Safety.

**Geotechnical Report**

- MM-6 Prior to the issuance of grading or building permits, the applicant shall submit a geotechnical report, prepared by a registered civil engineer or certified engineering geologist, to the Department of Building & Safety for review and approval. The geotechnical report shall assess potential consequences of any soil strength loss, estimation of settlement, lateral movement or reduction in foundation soil-bearing capacity, and discuss mitigation measures that may include building design consideration. Building design considerations shall include, but are not limited to, ground stabilization, selection of appropriate foundation type and depths, selection of appropriate structural systems to accommodate anticipated displacements or any combination of these measures.
- MM-7 The project shall comply with the conditions contained within the Department of Building & Safety's Geology and Soils Report Approval Letter for the proposed project, and as it may be subsequently amended or modified.

**Increased Noise Levels (Demolition, Grading and Construction Activities)**

- MM-8 Construction and demolition shall be restricted to the hours of 7:00 a.m. and 6:00 p.m., Monday through Friday, and 8:00 a.m. to 6:00 p.m. on Saturday.
- MM-9 Demolition and construction activities shall be scheduled so as to avoid operating several pieces of equipment simultaneously, which causes high noise levels.
- MM-10 The project contractor shall use power construction equipment with state-of-the-art noise shielding and muffling devices.

**Utilities (Local Water Supplies - Landscaping)**

- MM-11 The project shall comply with Ordinance No. 170,978 (Water Management Ordinance), which imposes numerous water conservation measures in landscape, installation, and maintenance (e.g. use drip irrigation and soak hoses in lieu of sprinklers to lower the amount of water lost to evaporation and overspray, set automatic sprinkler systems to irrigate during the early morning or evening hours to minimize water loss due to evaporation, and water less in the cooler months and during the rainy season).

MM-12 In addition to the requirements of the Landscape Ordinance, the Landscape Plan shall incorporate the following:

- a. Weather-based irrigation controller with rain shutoff,
- b. Matched precipitation (flow) rates for sprinkler heads,
- c. Drip/microspray/subsurface irrigation where appropriate,
- d. Minimum irrigation system distribution uniformity of 75 percent,
- e. Proper hydro-zoning, turf minimization and use of native / drought tolerant plant materials,
- f. Use of landscape contouring to minimize precipitation runoff, and
- g. A separate water meter (or submeter), flow sensor, and master valve shutoff shall be installed for irrigated landscape areas totaling 5,000 square feet and greater, to the satisfaction of the Department of Building & Safety.

**Utilities (Local Water Supplies - All New Construction)**

MM-13 If conditions dictate, the Department of Water and Power may postpone new water connections for this project until new water capacity is adequate.

MM-14 Install high-efficiency toilets (maximum 1.28gpf), including dual-flush water closets, high efficiency urinals (maximum 0.5 gpf), including no-flush or waterless urinals, in all restrooms as appropriate.

MM-15 Install restroom faucets with a maximum flow rate of 1.5 gallons per minute.

MM-16 A separate water meter (or submeter), flow sensor, and master valve shutoff shall be installed for all landscape irrigation

MM-17 Single-pass cooling equipment shall be strictly prohibited from use. Prohibition of such equipment shall be indicated on the building plans and incorporated into tenant lease agreements. (Single-pass cooling refers to the use of potable water to extract heat from processes equipment, e.g. vacuum pump, ice machines, by passing the water through equipment and discharging the heated water to the sanitary wastewater systems.)

**Utilities (Local Water Supplies – New Residential)**

MM-18 Install no more than one shower head per shower stall, having a flow rate no greater than 2.0 gallons per minute.

MM-19 Install and utilize only high-efficiency clothes washers (water factor of 6.0 or less) in the project, if proposed to be provided in either individual units and/or in a common laundry room (s). If such appliance is to be furnished by a tenant, this requirement shall be incorporated into the

lease agreement, and the applicant shall be responsible for ensuring compliance.

MM-20 Install and utilize only high-efficiency Energy Star-rated dishwashers in the project, if proposed to be provided. If such appliance is to be furnished by a tenant, this requirement shall be incorporated into the lease agreement and the applicant shall be responsible for ensuring compliance.

#### **Utilities (Solid Waste Recycling)**

MM-21 Recycling bins shall be provided at appropriate locations to promote recycling of paper, metal, glass, and other recyclable material. These bins shall be emptied and recycled accordingly as part of the project's solid waste disposal program.

MM-22 Prior to the issuance of any demolition or construction permit, the applicant shall provide a copy of the receipt or contract from a waste disposal company providing services to the project, specifying recycled waste services(s) to the satisfaction of the Department of Building & Safety. The demolition and construction contractor(s) shall only contract for waste disposal services with a company that recycles demolition and/or construction related wastes.

MM-23 To facilitate on-site separation and recycling of demolition and construction related wastes, the contractor(s) shall provide temporary waste separation bins onsite during demolition and construction. These bins shall be emptied and recycled accordingly as part of the project's regular solid waste disposal program.

#### **Utilities (Solid Waste Disposal)**

MM-24 All waste shall be disposed of properly. Use appropriately labeled recycling bins to recycle demolition and construction materials including solvents, water based paints, vehicle fluids, broken asphalt and concrete, bricks, metals, wood and vegetation. Non-recyclable materials/wastes shall be taken to an appropriate landfill. Toxic wastes must be discarded at a licensed, regulated disposal site.

16. **Construction Mitigation Conditions** - Prior to the issuance of a grading or building permit, or the recordation of the final map, the subdivider shall prepare and execute a Covenant and Agreement (Planning Department General Form CP-6770) in a manner satisfactory to the Planning Department, binding the subdivider and all successors to the following:

CM-1 That a sign be required on site clearly stating a contact/complaint telephone number that provides contact to a live voice, not a recording or voice mail, during all hours of construction, the construction site address,

and the tract map number. YOU ARE REQUIRED TO POST THE SIGN 7 DAYS BEFORE CONSTRUCTION IS TO BEGIN.

- Locate the sign in a conspicuous place on the subject site or structure (if developed) so that it can be easily read by the public. The sign must be sturdily attached to a wooden post if it will be free-standing.
- Regardless of who posts the site, it is always the responsibility of the applicant to assure that the notice is firmly attached, legible, and remains in that condition throughout the entire construction period.
- If the case involves more than one street frontage, post a sign on each street frontage involved. If a site exceeds five (5) acres in size, a separate notice of posting will be required for each five (5) acres or portion thereof. Each sign must be posted in a prominent location.

### **Air Quality**

- CM-2 All unpaved demolition and construction areas shall be wetted at least twice daily during excavation and construction, and temporary dust covers shall be used to reduce dust emissions and meet SCAQMD District Rule 403. Wetting could reduce fugitive dust by as much as 50 percent.
- CM-3 The owner or contractor shall keep the construction area sufficiently dampened to control dust caused by grading and hauling, and at all times provide reasonable control of dust caused by wind.
- CM-4 All loads shall be secured by trimming, watering or other appropriate means to prevent spillage and dust.
- CM-5 All materials transported off-site shall be either sufficiently watered or securely covered to prevent excessive amount of dust.
- CM-6 All clearing, grading, earth moving, or excavation activities shall be discontinued during periods of high winds (i.e., greater than 15 mph), so as to prevent excessive amounts of dust.
- CM-7 General contractors shall maintain and operate construction equipment so as to minimize exhaust emissions.

### **Noise**

- CM-8 The project shall comply with the City of Los Angeles Noise Ordinance No. 144,331 and 161,574, and any subsequent

ordinances, which prohibit the emission or creation of noise beyond certain levels at adjacent uses unless technically infeasible.

- CM-9 Construction and demolition shall be restricted to the hours of 7:00 a.m. to 6:00 p.m. Monday through Friday, and 8:00 a.m. to 6:00 p.m. on Saturday.
- CM-10 Construction and demolition activities shall be scheduled so as to avoid operating several pieces of equipment simultaneously, which causes high noise levels.
- CM-11 The project contractor shall use power construction equipment with state-of-the-art noise shielding and muffling devices.
- CM-12 The project sponsor must comply with the Noise Insulation Standards of Title 24 of the California Code Regulations, which insure an acceptable interior noise environment.

### **Grading**

- CM-13 Excavation and grading activities shall be scheduled during dry weather periods. If grading occurs during the rainy season (October 15 through April 1), construct diversion dikes to channel runoff around the site. Line channels with grass or roughened pavement to reduce runoff velocity.
- CM-14 Incorporate appropriate erosion control and drainage devices to the satisfaction of the Building and Safety Department shall be incorporated, such as interceptor terraces, berms, vee-channels, and inlet and outlet structures, as specified by Section 91.7013 of the Building Code, including planting fast-growing annual and perennial grasses in areas where construction is not immediately planned. These shall shield and bind the soil.
- CM-15 Stockpiles and excavated soil shall be covered with secured tarps or plastic sheeting.

### **General Construction**

- CM-16 Excavation and grading activities shall be scheduled during dry weather periods. If grading occurs during the rainy season (October 15 through April 1), construct diversion dikes to channel runoff around the site. Line channels with grass or roughened pavement to reduce runoff velocity.
- CM-17 Incorporate appropriate erosion control and drainage devices to the satisfaction of the Building and Safety Department shall be incorporated, such as interceptor terraces, berms, vee-channels, and inlet and outlet structures, as specified by Section 91.7013 of the Building Code, including planting fast-growing annual and

perennial grasses in areas where construction is not immediately planned. These shall shield and bind the soil.

- CM-18 Stockpiles and excavated soil shall be covered with secured tarps or plastic sheeting.
- CM-19 Cover and maintain dumpsters. Place uncovered dumpsters under a roof or cover with tarps or plastic sheeting.
- CM-20 Use gravel approaches where truck traffic is frequent to reduce soil compaction and limit the tracking of sediment into streets.
- CM-21 Conduct all vehicle/equipment maintenance, repair, and washing away from storm drains. All major repairs are to be conducted off-site. Use drip pans or drop clothes to catch drips and spills.

#### **DEPARTMENT OF CITY PLANNING - STANDARD SINGLE-FAMILY CONDITIONS**

SF-1. That approval of this tract constitutes approval of model home uses, including a sales office and off-street parking. If models are constructed under this tract approval, the following conditions shall apply:

1. Prior to recordation of the final map, the subdivider shall submit a plot plan for approval by the Division of Land Section of the Department of City Planning showing the location of the model dwellings, sales office and off-street parking. The sales office must be within one of the model buildings.
2. All other conditions applying to Model Dwellings under Section 12.22A, 10 and 11 and Section 17.05 O of the Los Angeles Municipal Code (LAMC) shall be fully complied with satisfactory to the Department of Building and Safety.

SF-2. That a landscape plan, prepared by a licensed landscape architect, be submitted to and approved by the Advisory Agency in accordance with CP-6730 prior to obtaining any grading or building permits before the recordation of the final map. The landscape plan shall identify tree replacement on a 1:1 basis by a minimum of 24-inch box trees for the unavoidable loss of desirable trees on the site.

In the event the subdivider decides not to request a permit before the recordation of the final map, a covenant and agreement satisfactory to the Advisory Agency guaranteeing the submission of such plan before obtaining any permit shall be recorded.

#### **BUREAU OF ENGINEERING - STANDARD CONDITIONS**

S-1. (a) That the sewerage facilities charge be deposited prior to recordation of the final map over all of the tract in conformance with Section 64.11.2 of the Los Angeles Municipal Code (LAMC).

- (b) That survey boundary monuments be established in the field in a manner satisfactory to the City Engineer and located within the California Coordinate System prior to recordation of the final map. Any alternative measure approved by the City Engineer would require prior submission of complete field notes in support of the boundary survey.
  - (c) That satisfactory arrangements be made with both the Water System and the Power System of the Department of Water and Power with respect to water mains, fire hydrants, service connections and public utility easements.
  - (d) That any necessary sewer, street, drainage and street lighting easements be dedicated. In the event it is necessary to obtain off-site easements by separate instruments, records of the Bureau of Right-of-Way and Land shall verify that such easements have been obtained. The above requirements do not apply to easements of off-site sewers to be provided by the City.
  - (e) That drainage matters be taken care of satisfactory to the City Engineer.
  - (f) That satisfactory street, sewer and drainage plans and profiles as required, together with a lot grading plan of the tract and any necessary topography of adjoining areas be submitted to the City Engineer.
  - (g) That any required slope easements be dedicated by the final map.
  - (h) That each lot in the tract complies with the width and area requirements of the Zoning Ordinance.
  - (i) That 1-foot future streets and/or alleys be shown along the outside of incomplete public dedications and across the termini of all dedications abutting unsubdivided property. The 1-foot dedications on the map shall include a restriction against their use of access purposes until such time as they are accepted for public use.
  - (j) That any 1-foot future street and/or alley adjoining the tract be dedicated for public use by the tract, or that a suitable resolution of acceptance be transmitted to the City Council with the final map.
  - (k) That no public street grade exceeds 15%.
  - (l) That any necessary additional street dedications be provided to comply with the Americans with Disabilities Act (ADA) of 1990.
- S-2. That the following provisions be accomplished in conformity with the improvements constructed herein:
- (a) Survey monuments shall be placed and permanently referenced to the satisfaction of the City Engineer. A set of approved field notes shall be

furnished, or such work shall be suitably guaranteed, except where the setting of boundary monuments requires that other procedures be followed.

- (b) Make satisfactory arrangements with the Department of Traffic with respect to street name, warning, regulatory and guide signs.
  - (c) All grading done on private property outside the tract boundaries in connection with public improvements shall be performed within dedicated slope easements or by grants of satisfactory rights of entry by the affected property owners.
  - (d) All improvements within public streets, private street, alleys and easements shall be constructed under permit in conformity with plans and specifications approved by the Bureau of Engineering.
  - (e) Any required bonded sewer fees shall be paid prior to recordation of the final map.
- S-3. That the following improvements are either constructed prior to recordation of the final map or that the construction is suitably guaranteed:

- (a) Construct on-site sewers to serve the tract as determined by the City Engineer.
- (b) Construct any necessary drainage facilities.
- (c) Install street lighting facilities to serve the tract as required by the Bureau of Street Lighting.

IMPROVEMENT CONDITION: Construct new street lights: two (2) on Fenton Avenue.

Notes:

The quantity of street lights identified may be modified slightly during the plan check process on illumination calculations and equipment selection.

Conditions set: 1) in compliance with a Specific Plan, 2) by LADOT, 3) by other legal instrument excluding the Bureau of Engineering condition S-3(i), requiring an improvement that will change the geometrics of the public roadway or driveway apron may require additional or the reconstruction of street lighting improvements as part of that condition.

- (d) Plant street trees and remove any existing trees within dedicated streets or proposed dedicated streets as required by the Street Tree Division of the Bureau of Street Maintenance. All street tree planting's shall be brought up to current standards. When the City has previously been paid for tree planting, the subdivider or contractor shall notify the Urban

Forestry Division ((213) 847-3077) upon completion of construction to expedite tree planting.

- (e) Repair or replace any off-grade or broken curb, gutter and sidewalk satisfactory to the City Engineer.
- (f) Construct access ramps for the handicapped as required by the City Engineer.
- (g) Close any unused driveways satisfactory to the City Engineer.
- (h) Construct any necessary additional street improvements to comply with the Americans with Disabilities Act (ADA) of 1990.
- (i) That the following improvements be either constructed prior to recordation of the final map or that the construction be suitably guaranteed:
  - 1) Improve Fenton Avenue adjoining the subdivision by the construction of a new 5-foot wide concrete sidewalk and landscaping of the parkway together with any necessary removal and construction of existing improvements including repair or reconstruction of the existing culverts under the said concrete sidewalk.

#### NOTES:

Any removal of the existing street trees shall require Board of Public Works approval. Satisfactory arrangements shall be made with the Los Angeles Department of Water and Power, Power System, to pay for removal, relocation, replacement or adjustment of power facilities due to this development. The subdivider must make arrangements for the underground installation of all new utility lines in conformance with Section 17.05-N of the Los Angeles Municipal Code (LAMC).

The final map must be recorded within 36 months of this approval, unless a time extension is granted before the end of such period.

The Advisory Agency hereby finds that this tract conforms to the California Water Code, as required by the Subdivision Map Act.

The subdivider should consult the Department of Water and Power to obtain energy saving design features which can be incorporated into the final building plans for the subject development. As part of the Total Energy Management Program of the Department of Water and Power, this no-cost consultation service will be provided to the subdivider upon his request.

**FINDINGS OF FACT (CEQA)**

The Environmental Staff Advisory Committee issued Mitigated Negative Declaration ENV-2013-2361 on November 6, 2013. The Committee found that potential negative impact could occur from the projects implementation due to:

Biology (Bird Habitat, Tree Removal)  
Geology (Seismic)  
Noise (Construction)  
Utilities (Water, Solid Waste)

The Deputy Advisory Agency, certifies that Mitigated Negative Declaration No. ENV-2013-2361-MND reflects the independent judgment of the lead agency and determined that this project would not have a significant effect upon the environment provided the potential impacts identified above are mitigated to a less than significant level through implementation of Conditions 14, 15, and 16 of the Tract's approval. Other identified potential impacts not mitigated by these conditions are mandatorily subject to existing City ordinances, (Sewer Ordinance, Grading Ordinance, Flood Plain Management Specific Plan, Xeriscape Ordinance, etc.) which are specifically intended to mitigate such potential impacts on all projects.

In accordance with Section 21081.6 of the Public Resources Code (AB3180), the Deputy Advisory Agency has assured that the above identified mitigation measures will be implemented by requiring reporting and monitoring as specified in Condition No. 14.

Furthermore, the Advisory Agency hereby finds that modification(s) to and/or correction(s) of specific mitigation measures have been required in order to assure appropriate and adequate mitigation of potential environmental impacts of the proposed use of this subdivision.

**FINDINGS OF FACT (SUBDIVISION MAP ACT)**

In connection with the approval of Tentative Tract No. 53664 the Advisory Agency of the City of Los Angeles, pursuant to Sections 66473.1, 66474.60, .61 and .63 of the State of California Government Code (the Subdivision Map Act), makes the prescribed findings as follows:

- (a) THE PROPOSED MAP WILL IS CONSISTENT WITH APPLICABLE GENERAL AND SPECIFIC PLANS.

The adopted Sylmar Community Plan designates the subject property Very Low II Residential with corresponding zones of RE11 and RE15. The property contains approximately 1.53-net acres (66,694 square feet), which will permit six lots consistent with the requirement of 11,000 square feet per lot in the existing (T)(Q)RE11-1VL-K zone. Therefore, the proposed development of six lots is allowable under the current land use designation and existing zone.

- (b) THE DESIGN AND IMPROVEMENT OF THE PROPOSED SUBDIVISION ARE CONSISTENT WITH APPLICABLE GENERAL AND SPECIFIC PLANS.

“Design” is defined under Section 66418 of the State Subdivision Map Act to mean (1) street alignment grades and width; (2) drainage and sanitary facilities and utilities, including alignments and grades thereof; (3) location and size of all required easements and rights-of-way; (4) fire roads and fire breakers; (5) lot size and configuration; (6) traffic access; (7) grading; (8) land to be dedicated for park or recreational purposes; and (9) other specific physical requirements in the plan and configuration with, or implementation of, the general plan or any applicable specific plan.

The development of six lots on a 1.53 net acre site is permitted by the existing (T)(Q)RE11-1VL-K zone. The rectangular lot cut pattern of the proposed subdivision is consistent with the surrounding design cut for the neighborhood and therefore consistent to the adopted Sylmar Community Plan.

- (c) THE SITE IS PHYSICALLY SUITABLE FOR THE PROPOSED TYPE OF DEVELOPMENT.

The development of this tract is an infill of an established single family residential neighborhood surrounding the subject site. The six lots created by this subdivision comply with the area requirements for the existing (T)(Q)RE11-1VL-K zone. The proposed density of six single family lots is permitted by the existing zone.

- (d) THE SITE IS PHYSICALLY SUITABLE FOR THE PROPOSED DENSITY OF DEVELOPMENT.

The site is one of the few under improved properties in the vicinity. The development of this tract is an infill of an otherwise single-family residential neighborhood.

The site is level and is not located in a slope stability study area, high erosion hazard area, or a fault-rupture study zone.

The Department of Building and Safety, Grading Division, has tentatively approved the tract map without conditions and subject to submittal of an acceptable soils engineering report in accordance with the Grading Regulations, Section 91.3000 of the Los Angeles Municipal Code (LAMC)) (relative to Division 70 of the Building Code).

- (e) THE DESIGN OF THE SUBDIVISION AND THE PROPOSED IMPROVEMENTS ARE NOT LIKELY TO CAUSE SUBSTANTIAL ENVIRONMENTAL DAMAGE OR SUBSTANTIALLY AND AVOIDABLY INJURE FISH OR WILDLIFE OR THEIR HABITAT.

The Initial Study prepared for the project identifies a potential adverse impact on fish or wildlife resources as far as plant life is concerned.

However mitigation measures are required as part of this approval which will mitigate the above mentioned impact to a less than significant level.

Furthermore, the project site, as well as the surrounding area is presently developed with residential structures and does not provide a natural habitat for either fish or wildlife.

(f) THE DESIGN OF THE SUBDIVISION AND THE PROPOSED IMPROVEMENTS ARE NOT LIKELY TO CAUSE SERIOUS PUBLIC HEALTH PROBLEMS.

There appears to be no potential public health problems caused by the design or improvement of the proposed subdivision.

The development is required to be connected to the City's sanitary sewer system, where the sewage will be directed to the LA Hyperion Treatment Plant, which has been upgraded to meet Statewide ocean discharge standards. The Bureau of Engineering has reported that the proposed subdivision does not violate the existing California Water Code because the subdivision will be connected to the public sewer system and will have only a minor incremental impact on the quality of the effluent from the Hyperion Treatment Plant.

(g) THE DESIGN OF THE SUBDIVISION AND THE PROPOSED IMPROVEMENTS WILL NOT CONFLICT WITH EASEMENTS ACQUIRED BY THE PUBLIC AT LARGE FOR ACCESS THROUGH OR USE OF PROPERTY WITHIN THE PROPOSED SUBDIVISION.

No such easements are known to exist. Needed public access for roads and utilities will be acquired by the City prior to recordation of the proposed tract.

(h) THE DESIGN OF THE PROPOSED SUBDIVISION WILL PROVIDE, TO THE EXTENT FEASIBLE, FOR FUTURE PASSIVE OR NATURAL HEATING OR COOLING OPPORTUNITIES IN THE SUBDIVISION. (REF. SECTION 66473.1)

- 1) In assessing the feasibility of passive or natural heating or cooling opportunities in the proposed subdivision design, the applicant has prepared and submitted materials which consider the local climate, contours, configuration of the parcel(s) to be subdivided and other design and improvement requirements.
- 2) Providing for passive or natural heating or cooling opportunities will not result in reducing allowable densities or the percentage of a lot which may be occupied by a building or structure under applicable planning and zoning in effect at the time the tentative map was filed.
- 3) The lot layout of the subdivision has taken into consideration the maximizing of the north/south orientation.
- 4) The topography of the site has been considered in the maximization of passive or natural heating and cooling opportunities.

- 5) In addition, prior to obtaining a building permit, the subdivider shall consider building construction techniques, such as overhanging eaves, location of windows, insulation, exhaust fans; planting of trees for shade purposes and the height of the buildings on the site in relation to adjacent development.

These findings shall apply to both the tentative and final maps for Tract No. 53664.

MICHAEL J. LOGRANDE  
Director of Planning

  
 MARC WOERSCHING  
 Deputy Advisory Agency

MJL:MW:NR:mkc

Note: If you wish to file an appeal, it must be filed within 10 calendar days from the decision date as noted in this letter. For an appeal to be valid to the City Planning Commission, it must be accepted as complete by the City Planning Department and appeal fees paid, prior to expiration of the above 10-day time limit. Such appeal must be submitted on Master Appeal Form No. CP-7769 at the Department's Public Offices, located at:



Figueroa Plaza  
 201 North Figueroa Street  
 4th Floor  
 Los Angeles, CA 90012  
 (213) 482-7077

Marvin Braude San Fernando  
 Valley Constituent Service Center  
 6262 Van Nuys Boulevard, Room 251  
 Van Nuys, CA 91401  
 (818) 374-5050

**\*Please note the cashiers at the public counters close at 3:30 PM.**

Forms are also available on-line at <http://cityplanning.lacity.org/>

The time in which a party may seek judicial review of this determination is governed by California Code of Civil Procedure Section 1094.6. Under that provision, a petitioner may seek judicial review of any decision of the City pursuant to California Code of Civil Procedure Section 1094.5, only if the petition for writ of mandate pursuant to that section is filed no later than the 90<sup>th</sup> day following the date on which the City's decision becomes final.



LYLE ST. PADDOCK ST. FENTON AVENUE ASTORIA ST.

FD. S&T NO REF.

TT 53664

# TENTATIVE TRACT L.A. NO: 53664

1. OWNER:  
MR. BENNY SILVA  
563 S. BRAND BLVD  
SAN FERNANDO, CA 91340  
(818) 207-1117
2. SUBDIVIDER:  
MR. BENNY SILVA  
563 S. BRAND BLVD  
SAN FERNANDO, CA 91340  
(818) 207-1117
3. REPRESENTATIVE:  
RICHARD PRUTZ, P.E.  
PRUTZ & ASSOCIATES  
2942 SCOTT ROAD  
BURBANK, CA 91504  
(818) 843-0593
4. ZONE: (T) (Q) RE11-1VL-K
5. A.P.N. 2503-009-028
6. NOTE: NO OAK TREES ON SUBJECT PROPERTY
7. THERE ARE NO KNOWN POTENTIALLY DANEROUS AREAS WITHIN THIS PROPOSED DEVELOPMENT.
8. PUBLIC SEWERS ARE AVAILABLE IN FENTON AVE.
9. SITE ADDRESS: 13600 FENTON AVENUE.

### AREA CALCULATIONS

Lot	Area (s.f.)
1	11,194.25
2	11,100.00
3	11,100.00
4	11,100.00
5	11,100.00
6	11,100.00
Sub-total:	66,694.25
Dedicate to St:	902.62
7.	367,733.13
Total:	435,330

SCALE: 1" = 40' (1980 ADJ.)  
DATE: 08 MARCH 2002



*Richard Prutz*

### TOPOGRAPHIC SURVEY

OF A PORTION OF BLOCK 16, OF THE MACLAY RANCHO, M.R. 37-5/6, RECORDS OF LOS ANGELES COUNTY

DATE OF SURVEY: JULY 2001

### PREPARED BY


WILSON SURVEYING, INC.  
11521 DONA TERESA DR.  
STUDIO CITY CA. 91604  
(323)-650-3900  
JOB NO. 2005

### BENCH MARK

WIRE SPIKE IN SE CURB ASTORIA ST., 1 FT. NE OF BC CURB RET NE OF ELDRIDGE AVE. CITY OF L.A. NO. 03-06362 ELEV. 1467.25

### PRUTZ & ASSOCIATES

CIVIL ENGINEERING - LAND PLANNING  
2942 SCOTT ROAD BURBANK, CA 90504-2318  
PHONE 818-843-0593 FAX 818-846-0693



VICINITY MAP  
NO SCALE